# CONSERVATION PLAN MAP

Smith Family Farms, LLC - Tract 2208

Smith Family Farms, LLC
4820 Cross Keys Road
Harrisonburg, Rockingham County, VA 22801

FARM: 4417 TRACT: 2208 WATERSHED: 0207
ACC ID: 26051004417

APPROXIMATE CROPLAND ACRES - 214.0
APPROXIMATE PASTURE ACRES - 96.0
ALL ACRES AND BOUNDARIES ARE APPROXIMATE

- Cropland
- Pasture
- Barnyard / heavy use area
- Riparian forest buffer (planned and existing)
- Perennial stream - Cub Run, 3,150 ft frontage

# SOILS MAP

Smith Family Farms, LLC - Tract 2208

## Soils Inventory Report

| Symbol | Map Unit Name | Acres | Percent |
|---|---|---|---|
| CnB | Caneyville silt loam, 2 to 6 percent slopes | 18.4 | 6% |
| CrD | Carbo-Rock outcrop complex, 15 to 25 percent slopes | 11.2 | 4% |
| FaA | Frederick silt loam, 0 to 2 percent slopes | 44.1 | 14% |
| GgA | Guernsey silt loam, 0 to 2 percent slopes | 52.6 | 17% |
| InA | Inman silt loam, 0 to 2 percent slopes | 88.3 | 28% |
| MnB | Murrill loam, 2 to 7 percent slopes | 61.0 | 20% |
| W | Water | 2.4 | 1% |
| WeC | Weikert channery silt loam, 8 to 15 percent slopes | 32.0 | 10% |
| **Total:** | | **310.0** | **100%** |

# CONSERVATION PLAN

Practice schedule - Tract 2208

**OBJECTIVE**
To maintain a viable corn silage and small grain rotation while reducing nutrient and sediment delivery to Cub Run, and to improve forage distribution for the cow-calf herd.

**RESOURCE CONCERNS**
Sheet and rill erosion on cropland slopes above the stream.
Livestock have direct access to Cub Run in the lower pasture block.
Nutrient management records incomplete for the east fields.

**Associated Ag Land** **Tract: 2208**

**Cover Crop - 340**
Cereal rye drilled following corn silage harvest. Not harvested. No fall nutrient application planned.

| | Planned | | | Applied | |
|---|---|---|---|---|---|
| Field | Amount | Month | Year | Amount | Date |
| 12 | 64.0 ac | 9 | 2026 | | |
| 14 | 49.5 ac | 9 | 2026 | | |
| 17 | 38.0 ac | 9 | 2026 | | |
| | | | Total: 151.5 ac | | |

**Residue and Tillage Management, No Till - 329**
Continuous no-till on all cropped acres. In place since 2019. Cost-shared under EQIP contract 68-3A75-19-112, which expired in 2024.

| | Planned | | | Applied | |
|---|---|---|---|---|---|
| Field | Amount | Month | Year | Amount | Date |
| 12 | 64.0 ac | 4 | 2019 | 64.0 ac | 5/2019 |
| 14 | 49.5 ac | 4 | 2019 | 49.5 ac | 5/2019 |
| 17 | 38.0 ac | 4 | 2019 | 38.0 ac | 5/2019 |
| | | | Total: 151.5 ac | | |

**Nutrient Management - 590**
Whole-farm plan written 2024. Reductions reported to Virginia DEQ for the 2025 reporting year.

| | Planned | | | Applied | |
|---|---|---|---|---|---|
| Field | Amount | Month | Year | Amount | Date |
| ALL | 214.0 ac | 3 | 2024 | 214.0 ac | 3/2024 |
| | | | Total: 214.0 ac | | |

**Riparian Forest Buffer - 391**
Establish a 75-foot average width hardwood buffer along the west bank of Cub Run where the field edge currently abuts the channel. Not yet installed.

| | Planned | | | Applied | |
|---|---|---|---|---|---|
| Field | Amount | Month | Year | Amount | Date |
| 21 | 5.4 ac | 11 | 2026 | | |
| 22 | 3.1 ac | 11 | 2026 | | |
| | | | Total: 8.5 ac | | |

**Riparian Forest Buffer - 391**
Existing 40-foot buffer on the east bank, planted 2016 under CREP. Retained, no further work planned.

| | Planned | | | Applied | |
|---|---|---|---|---|---|
| Field | Amount | Month | Year | Amount | Date |
| 23 | 4.2 ac | 3 | 2016 | 4.2 ac | 4/2016 |
| | | | Total: 4.2 ac | | |

**Prescribed Grazing - 528**
Subdivide the lower pasture into six paddocks and rotate the cow-calf herd on a flexible schedule. No fixed move interval specified.

| | Planned | | | Applied | |
|---|---|---|---|---|---|
| Field | Amount | Month | Year | Amount | Date |
| 31 | 58.0 ac | 5 | 2027 | | |
| 32 | 38.0 ac | 5 | 2027 | | |
| | | | Total: 96.0 ac | | |

**Fence - 382**
Exclusion fencing along both banks of Cub Run and perimeter fencing for the new paddock divisions.

| | Planned | | | Applied | |
|---|---|---|---|---|---|
| Field | Amount | Month | Year | Amount | Date |
| 31 | 4,200 ft | 5 | 2027 | | |
| | | | Total: 4,200 ft | | |

**Watering Facility - 614**
Two frost-free troughs with buried supply line from the existing well to serve the new paddocks. Nearest well is 900 feet from the paddock centre.

| | Planned | | | Applied | |
|---|---|---|---|---|---|
| Field | Amount | Month | Year | Amount | Date |
| 31 | 2 no | 5 | 2027 | | |
| | | | Total: 2 facilities | | |

**Heavy Use Area Protection - 561**
Concrete pad and roof runoff control at the existing feeding area adjacent to the barnyard.

| | Planned | | | Applied | |
|---|---|---|---|---|---|
| Field | Amount | Month | Year | Amount | Date |
| 40 | 0.8 ac | 8 | 2027 | | |
| | | | Total: 0.8 ac | | |

**Conservation Crop Rotation - 328**
Move fields 12 and 14 from continuous corn silage into a corn-small grain-soybean rotation.

| | Planned | | | Applied | |
|---|---|---|---|---|---|
| Field | Amount | Month | Year | Amount | Date |
| 12 | 64.0 ac | 4 | 2027 | | |
| 14 | 49.5 ac | 4 | 2027 | | |
| | | | Total: 113.5 ac | | |

---

**NOTES**
Producer is interested in rotational grazing but has not committed to a move schedule. Water infrastructure is the limiting factor. Producer has asked about planting trees in the pasture for shade.
Verification responsibility not yet assigned.

---



USDA is an equal opportunity provider, employer and lender.